MUZRAI DEPARTMENT.

Notice R. O. C. 487—S. of 16-17, dated 13th March 1918.

Notice is hereby given that sealed tenders will be received at the office of the Amildar, Arkalgud Taluk, up to 10th April 1918, for repairing the Sri Agasteswaraswami temple at Ramanathpur in the Arkalgud Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by June 1918.

2. The plan and detailed estimate may be seen at the Taluk Office at Arkalgud and conditions of the contract ascertained from the Amildar between 11 A.M. and 5 P.M., general holidays excepted.

3. Tenders should be submitted duly accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Pro-notes as earnest money and be superscribed "Tender for repairing the Sri Agasteswaraswamy temple at Ramanathpur," in default of which, the tender will be liable to be rejected.

5. The final acceptance of the tender will rest with the Deputy Commissioner, Hassan District, who does not bind himself to accept the lowest of any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days from the date of the acceptance of the tender which will be duly intimated to the person concerned, necessary contract bond should be executed failing which the contract will be considered cancelled and the earnest money forfeited.

7. On acceptance of one of the tenders the earnest money of the other rejected tenders will be returned.

Estimated work and quantity.

Details of work to be done	Per	Estimated quantity
Kalyanamantapam and Yagasala.		
Removing old earth and jelly	Cubic yard ...	55
Foundation.		
Excavating earth and packing with jelly	Do ...	49
Removing old concrete and brick works	Cubic feet ...	407
Do stone slabs	Do ...	836
Do concrete work	Do ...	234
Do mortar and stone works	Do ...	1,126
Refixing old pillars and beams	Do ...	1,144
Brick, jelly and mortar work	Do ...	123
Brick and mortar work	Do ...	600
Upper storey flooring 9" thick	Square ...	7-20
Roofing with slabs of three layers	Do ...	11-0
Constructing a wall with burnt stone slabs	Cubic feet ...	177
Teakwood doors complete work	Square feet ...	18
Teakwood windows complete work	Do ...	7
Plastering with mortar	Square ...	3-00
Metalling with earth and jelly and water	Cubic yard ...	30-00
Concrete plastering	Square ...	3-28
Plastering of cornice	Feet ...	55
Architectural cornice work	Do ...	1
Dismantling old brick work and removing it	Cubic feet ...	169
Jelly in mortar	Do ...	630
Whitewashing	Square ...	10-08
Compound.		
Removing earth and jelly	Cubic yard ...	13
Do stone slabs	Cubic feet ...	359
Excavating foundation and refilling	Cubic yard ...	10
Brick work with mortar	Cubic feet ...	997
Plastering with mortar	Square ...	13-09
Coping with brick 9" thick	Cubic feet ...	90
Sundry work	Lump sum about	Rs. 4.

C. LAKSHMANA RAO,
For *Deputy Commissioner, Hassan District.*